

Revised..... Bid for removing the existing speakers from the IFK Arena, and installing new JBL AWC129 All Weather Arena speakers in the IFK Arena.

*****Additional items added to this proposal are; the added 300ft of 12 gauge wire for all 9 speakers, the 266 Dual dbx compressor for vocal channels and the labor required to install these additional items.*****

The SoundMan will remove the old speakers and install the new JBL speakers at the most efficient location above the glass, to provide the best possible sound for the bleachers and for the ice surface for large events.

The SoundMan will provide;

9 JBL AWC 129 speakers at a cost of \$9500

*****550ft of double insulated, oxidized 12gauge copper speaker cable at a cost of \$480*****revised

Ashley MQX 2310 Stereo EQ at a cost of \$675

***** (like new) 266 Dual dbx compressor for vocal channel level control at a cost of \$250*****

Quality Podium Condenser mic (with mute switch), in penalty box at a cost of \$300

9 metal mounting brackets and safety cables at a cost of \$400

Properly cleaning of all old system components at a cost of \$200

Rental equipment for safe installation at a cost of \$390

Misc: AC and audio patch cords, tie wraps, electrical connectors etc.... \$100

*****prices include tax and shipping costs*****

The SoundMan will provide the "Proper Installation" of all the equipment and materials listed above at a cost of \$3400.....over and above and not including the equipment and materials listed above.

Work To Be Performed;..... (I will hire my own assistant).

Removing old speakers and their mounting hardware.

Rerouting old 16 gauge speaker cables, to hide them from sight for possible future use.

Installing new oxidized 12 gauge speaker cables for all 9 new speakers.

Continued on Page 2.....

B Harris

Mark McLaughlin

Installing 9 new speakers and their new metal mounting brackets to the beams with safety cables.

Aiming all speakers with laser and ears.

Proper electrical loading of amplifiers.

Install condenser podium mic mounting bracket and microphone in penalty box.

Adjust proper gain structure between components.

Install and adjust vocal compressor

Balancing of levels, between channels and amplifiers.

EQ'ing separate listening areas.

Adjust audio Limiter for system protection.

****It is understood that the SoundMan will be given the use of the Arena's lift (free of charge) with the safety harness, for the duration of this contract****

Total cost of this contract is \$15,700 CDN Funds. ***No HST Required***

Customer agrees to pay \$10,000 in advance for the materials to be ordered.

After the advanced payment of \$10,000 for materials is received by The SoundMan;

The customer agrees to pay the balance owing for this contract of \$5,700 upon the completion of the job, after final sound check is completed.

The SoundMan Cell 807-275-9031 Home 807-274-5633

Brian Harris

1006 colonization Rd W

Ft Frances on P9A-2T4

The Soundman is willing to discuss any additional work not mentioned in this contract.

It is understood that The SoundMan is proving only the work listed in this 2 page document.

Any additional equipment or work required for this job that is not discussed in this document is NOT presumed to be included.

B Harris

Mark McEug