

1. TENDER FOR THE CONSTRUCTION OF

**2015 Road Reconstruction, Watermain and Sewer Replacement
Tender No. 15-OF-10**

**PHAIR AVENUE (From Third St. East to Sixth St. East)
NELSON STREET (From Butler Ave. 100 metres Easterly)
KINGS HIGHWAY 11/71 (From Wright Ave. to York Ave.)**

1.1 TENDER PRICE

Tender By:

Bay City Contractors Inc.

Contractor

1123 Russell Street, Thunder Bay, Ontario

Address

April 23, 2015

Date

hereinafter called the "Tenderer"

To: **The Corporation of the Town of Fort Frances
320 Portage Avenue
Fort Frances, Ontario
P9A 3P9**

Hereinafter called the "Owner"

- 1.1.1 (We), the undersigned, having fully examined the locality and Place of the Work, having fully investigated the conditions of the Work, having read and understood the Contract Documents (comprised of the tendering information, supplementary general conditions, general conditions, specifications and drawings, including all supplements, addenda and revisions to same to the date of this tender) and having secured all of the information necessary to enable the submission of this tender, hereby agree and offer to perform the totality of the Work described in the Contract Documents, in accordance with the Contract Documents, for the total Tender Price (including H.S.T.) of:

Six million, three hundred ten thousand, one hundred and four dollars and
nineteen cents----- (\$6,310,104.19.)

1. TENDER FOR THE CONSTRUCTION OF

**2015 Road Reconstruction, Watermain and Sewer Replacement
Tender No. 15-OF-10**

**PHAIR AVENUE (From Third St. East to Sixth St. East)
NELSON STREET (From Butler Ave. 100 metres Easterly)
KINGS HIGHWAY 11/71 (From Wright Ave. to York Ave.)**

1.1 TENDER PRICE

Tender By:

Contractor

Address

Date

hereinafter called the "Tenderer"

To: **The Corporation of the Town of Fort Frances
320 Portage Avenue
Fort Frances, Ontario
P9A 3P9**

Hereinafter called the "Owner"

- 1.1.1 (We), the undersigned, having fully examined the locality and Place of the Work, having fully investigated the conditions of the Work, having read and understood the Contract Documents (comprised of the tendering information, supplementary general conditions, general conditions, specifications and drawings, including all supplements, addenda and revisions to same to the date of this tender) and having secured all of the information necessary to enable the submission of this tender, hereby agree and offer to perform the totality of the Work described in the Contract Documents, in accordance with the Contract Documents, for the total Tender Price (including H.S.T.) of:

(\$.....)

1.2 CONTINGENCIES AND ALLOWANCES

- 1.2.1 We agree that the Tender Price includes the contingency sum of **\$250,000** and that no part of this sum shall be expended without the written direction of the Contract Administrator, and any part not so expended shall be deducted from the Contract Price.

1.3 QUANTITIES

- 1.3.1 The Tender Price is compiled from the Schedule of Prices included hereinafter. The quantities in the schedule being approximate, we agree that the final valuation will be made on the basis of actual quantities measured during and on completion of the Work at the unit prices in the schedule.

1.4 ADDITIONS AND DEDUCTIONS

- 1.4.1 The Tenderer agrees that, if this tender is accepted by the Owner:

- (i) it will carry out any additional or extra work (including the supplying of any additional Products pertaining thereto) or will delete any work as may be required by the Contract Administrator in accordance with the Contract; and,
- (ii) the carrying out of any work referred to in paragraph (i) above or the issuance by the Contract Administrator of a Contract Change Order relating to such work or the acceptance by the Tenderer of such Contract Change Order shall not, except as expressly stated in such Contract Change Order, waive, affect or vary any of the terms of the Contract or of an Contract Change Order previously issued by the Contract Administrator or any of the rights of the Owner or of the Contract Administrator under the Contract.

- 1.4.2 The Tenderer agrees that, if this tender is accepted by the Owner the prices applicable to work referred to in paragraph 1.4.1 above shall be determined as follows:

- (i) The Schedule of Tender Prices shall apply where applicable;
- (ii) If the above Schedule is inapplicable the prices shall be determined in accordance with the General Conditions as amended by the Supplementary General Conditions.

- 1.4.3 The Tenderer agrees that it is not entitled to payment of the Contingency Allowance except for additional work carried out by him in accordance with the Contract and only to the extent of such additional work, as authorized by the Contract Administrator in writing.

1.5 ADDENDA

1.5.1 We agree that we have received Addenda 1 to 4 inclusive, and includes for the provisions set out in such Addenda.

1.6 CONTRACT TIME

1.6.1 We agree to commence the Work and to proceed continuously to to complete the Work as follows:

<u>Work Description</u>	<u>Commencement Date</u>	<u>Comple</u>
1) Hwy 11/71, Phair Ave. 3 rd to 5 th	May 11 th , 2015	Septemb
2) Phair Ave. 5 th to 6 th , Nelson Street	May 17 th , 2016	Septemb

1.7 TENDER ITEM REFERENCES AND DELETIONS

1.7.1 Where in the Form of Tender (Schedule of Tender Prices) under the headed OPS Spec. No., a number is shown, such number shall be taken and refer to the Ontario Provincial Standard Specifications (OPSS). section number is referenced refer to the applicable specification in document.

1.7.2 Where in the Form of Tender under the column headed OPS Spec N "SP" appear, such initials shall be taken to mean and refer to the "Sp Provisions".

1.7.3 For those Tender items noted with an asterisk * in the Schedule of T are considered to be provisional items and the Owner may delete all of the item price to Contract award without affecting the remaining C prices, without penalty or recourse.

1.7.4 The Owner reserves the right to delete all or any portion of the v Contract award and during the construction period without a remaining Contract prices, without penalty or recourse.

1.8 SCHEDULE OF TENDER PRICES

- A. For those Tender Items identified by the notation (P) in the "Unit" column, measurement is by Plan Quantity. Tender items not identified by the notation (P) actual measurement for payment will be made in the stipulated Unit or Lump Sum as specified in the contract.

ITEM NO.	OPS SPEC.	DESCRIPTION	EST. QTY	UNIT	UNIT BID PRICE	TOTAL BID PRICE
PHAIR AVENUE (3rd St. E to 5th St. E) - Drawing A1-348468-P1						
Section A - Grading						
A.001	206, SP	Earth Excavation (Grading)	1,690	m ³ (P)	\$ 12.00	\$ 20,280
A.002	310, SP	Hot Mix HL4 Asphalt	345	t	\$ 248.00	\$ 85,560
A.003	314, SP	Granular 'A'	1,170	t	\$ 22.00	\$ 25,740
A.004	314, SP	Granular 'B' (Type 1)	2,900	t	\$ 16.00	\$ 46,400
A.005	510, SP	Removal of Asphalt Pavement (Full Depth)	2,503	m ² (P)	\$ 4.00	\$ 10,012
A.006	510, SP	Removal of Curb and Gutter	437	m (P)	\$ 10.00	\$ 4,370
A.007	510, SP	Removal of Concrete Sidewalk	524	m ² (P)	\$ 20.00	\$ 10,480
A.008	351, SP	Concrete Sidewalk	296	m ²	\$ 181.00	\$ 53,576
A.009	510,351, SP	Remove and Replace Concrete Driveways	179	m ²	\$ 145.00	\$ 25,955
A.010	353, SP	Concrete Curb and Gutter	420	m	\$ 130.00	\$ 54,600
A.011	353, SP	Concrete Gutter Outlets	4	ea	\$ 1,005.00	\$ 4,020
A.012	Section 02930	100 mm Topsoil and Sod	1,196	m ²	\$ 12.00	\$ 14,352
A.013	510, SP	Boulevard Works Stripping and Removal	1	LS	\$ 11,500.00	\$ 11,500
Total Section A - Grading						\$ 366,845.00
PHAIR AVENUE (3rd St. E to 5th St. E) - Drawing A1-348468-P1						
Section B - Storm Sewers						
B.001	510, SP	Remove Existing Catchbasins and Manholes	7	ea (P)	\$ 1,000.00	\$ 7,000.00
B.002	510, SP	Remove Existing Catchbasin Leads	93	m (P)	\$ 25.00	\$ 2,325.00
B.003	510, SP	Remove Existing 450 mm Storm Sewer	10	m	\$ 30.00	\$ 300.00
B.004	410, SP	200 mm PVC SDR 35 Catchbasin Leads	51	m	\$ 200.00	\$ 10,200.00
B.005	410, SP	450 mm Storm Sewer	10	m	\$ 1,100.00	\$ 11,000.00
B.006	407, SP	Ditch Inlet Structures (OPSD 705.030 Flat)	4	ea	\$ 4,000.00	\$ 16,000.00
B.007	407, SP	Storm Manhole #1 (OPSD 705.010)	1	ea	\$ 4,700.00	\$ 4,700.00
Total Section B - Storm Sewers						\$ 51,525.00
PHAIR AVENUE (3rd St. E to 5th St. E) - Drawing A1-348468-P1						
Section C - Watermain						
C.001	510,441, SP	Remove and Replace Existing 150 mm Watermain with New 150 mm PVC DR 18 Class 150 Watermain	206	m	\$ 465.00	\$ 95,790.00
C.002	441, SP	150 mm Water Valve and Box	4	ea	\$ 2,400.00	\$ 9,600.00
C.003	SP	50 mm Rigid Styrofoam Insulation	63	m ²	\$ 55.00	\$ 3,465.00
C.004	510, 441, SP	Remove and Replace Existing 300 Watermain with New 300 mm PVC DR 18 Class 150 Watermain	32	m	\$ 715.00	\$ 22,880.00
C.005	441, SP	300 mm Water Valve and Box	2	ea	\$ 5,300.00	\$ 10,600.00
C.006	441, SP	Remove and Replace 19 mm Copper Water Service and Curb Stops	18	ea	\$ 3,000.00	\$ 54,000.00
C.007	510, 441, SP	Remove and Replace Hydrant Set	1	ea	\$ 12,200.00	\$ 12,200.00
C.008	441, SP	Hydrant Set	1	ea	\$ 12,000.00	\$ 12,000.00
C.009	441, SP	Temporary Water Service	1	LS	\$ 5,000.00	\$ 5,000.00
Total Section C - Watermain						\$ 225,535.00

ITEM NO.	OPS SPEC.	DESCRIPTION	EST. QTY	UNIT	UNIT BID PRICE	TOTAL BID PRICE
PHAIR AVENUE (3rd St. E to 5th St. E) - Drawing A1-348468-P1						
Section D - Sanitary						
D.001	510, SP	Remove Existing 300 mm Sanitary Sewer	209	m (P)	\$ 25.00	\$ 5,225.00
D.002	510, SP	Remove Existing Sanitary Manholes	2	ea	\$ 1,500.00	\$ 3,000.00
D.003	410, SP	300 mm PVC SDR Sanitary Sewer	209	m	\$ 530.00	\$ 110,770.00
D.004	704, SP	Sanitary Manholes	2	ea	\$ 10,000.00	\$ 20,000.00
D.005	410, SP	Remove and Replace Existing 150 mm Sanitary Services	18	ea	\$ 2,500.00	\$ 45,000.00
D.006	410, SP	Temporary Sewer Service	1	LS	\$ 8,500.00	\$ 8,500.00
D.007	409, SP	Closed Circuit Television Inspection of 300 m Sanitary Sewer Mainline	209	m	\$ 13.00	\$ 2,717.00
D.008	SP	Sanitary Sewer Bedding Upgrade (Geotextile) *	209	m	\$ 7.00	\$ 1,463.00
D.009	SP	Sanitary Sewer Bedding Upgrade (Crushed Stone) *	209	m	\$ 15.00	\$ 3,135.00
Total Section D - Sanitary						\$ 199,810.00
TOTAL PHAIR AVENUE (3rd St. E to 5th St. E)						\$ 843,715.00
PHAIR AVENUE (5th St. E to 6th St. E.) - Drawing A1-348468-P2						
Section A - Grading						
A.001	206, SP	Earth Excavation (Grading)	1,492	m ³ (P)	\$ 12.00	\$ 17,904
A.002	310, SP	Hot Mix HL4 Asphalt	295	t	\$ 256.00	\$ 75,520
A.003	314, SP	Granular 'A'	995	t	\$ 22.00	\$ 21,890
A.004	314, SP	Granular 'B' (Type 1)	2,620	t	\$ 16.00	\$ 41,920
A.005	510, SP	Removal of Asphalt Pavement (Full Depth)	-2,157	m ² (P)	\$ 4.00	\$ 8,628
A.006	510, SP	Removal of Curb and Gutter	372	m (P)	\$ 10.00	\$ 3,720
A.007	510, SP	Removal of Concrete Sidewalk	310	m ² (P)	\$ 20.00	\$ 6,200
A.008	351, SP	Concrete Sidewalk	104	m ²	\$ 186.00	\$ 19,344
A.009	510,351, SP	Remove and Replace Concrete Driveways	137	m ²	\$ 208.00	\$ 28,496
A.010	353, SP	Concrete Curb and Gutter	372	m	\$ 142.00	\$ 52,824
A.011	353, SP	Concrete Gutter Outlets	2	ea	\$ 1,170.00	\$ 2,340
A.012	Section 02930	100 mm Topsoil and Sod	1,206	m ²	\$ 12.00	\$ 14,472
A.013	510, SP	Boulevard Works Stripping and Removal	1	LS	\$ 10,000.00	\$ 10,000
Total Section A - Grading						\$ 303,258.00
PHAIR AVENUE (5th St. E to 6th St. E.) - Drawing A1-348468-P2						
Section B - Storm Sewers						
B.001	407, SP	Ditch Inlet Structures (OPSD 705.030 Flat)	2	ea	\$ 4,100.00	\$ 8,200.00
B.002	410, SP	200 mm PVC SDR 35 Catchbasin Leads	37	m	\$ 200.00	\$ 7,400.00
Total Section B - Storm Sewers						\$ 15,600.00

* Provisional Item

ITEM NO.	OPS SPEC.	DESCRIPTION	EST. QTY	UNIT	UNIT BID PRICE	TOTAL BID PRICE
PHAIR AVENUE (5th St. E to 6th St. E.) - Drawing A1-348468-P2						
Section C - Watermain						
C.001	510, SP	Remove Existing 150 mm Watermain DELETED	200	m	\$	\$
C.002	510,441, SP	Remove and Replace Existing Watermain with New 150 mm PVC DR 18 Class 150 Watermain	184	m	\$ 483.00	\$ 88,872.00
C.003	441, SP	150 mm Water Valve and Box	1	ea	\$ 2,400.00	\$ 2,400.00
C.004	510,441,SP	Remove and Replace Existing 300 Watermain with New 300 mm PVC DR 18 Class 150 Watermain	32	m	\$ 715.00	\$ 22,880.00
C.005	441, SP	300 mm Water Valve and Box	2	ea	\$ 5,300.00	\$ 10,600.00
C.006	SP	50 mm Rigid Styrofoam Insulation	68	m ²	\$ 55.00	\$ 3,740.00
C.007	441, SP	Remove and Replace 19 mm Copper Water Service and Curb Stops	26	ea	\$ 3,000.00	\$ 78,000.00
C.008	441, SP	Remove and Replace Hydrant Set	2	ea	\$ 12,200.00	\$ 24,400.00
C.009	441, SP	Temporary Water Service	1	LS	\$ 4,500.00	\$ 4,500.00
Total Section C - Watermain						\$ 235,392.00
PHAIR AVENUE (5th St. E to 6th St. E.) - Drawing A1-348468-P2						
Section D - Sanitary						
D.001	408, SP	Supply, Adjust, and Install New Adjustable Manhole Frame and Cover on Existing Sanitary Storm Manholes	1	ea	\$ 1,350.00	\$ 1,350.00
D.002	510, SP	Remove Existing 300 mm Sanitary Sewer	188	m	\$ 25.00	\$ 4,700.00
D.003	510, SP	Remove Existing Sanitary Manhole	1	ea	\$ 1,000.00	\$ 1,000.00
D.004	410, SP	300 mm PVC SDR Sanitary Sewer	188	m	\$ 532.00	\$ 100,016.00
D.005	407, SP	Sanitary Manholes	1	ea	\$ 10,000.00	\$ 10,000.00
D.006	410, SP	Remove and Replace Existing 150 mm Sanitary Services	26	ea	\$ 2,900.00	\$ 75,400.00
D.007	410, SP	Temporary Sewer Service	1	LS	\$ 7,500.00	\$ 7,500.00
D.008	409, SP	Closed Circuit Television Inspection of 300 m Sanitary Sewer Mainline	188	m	\$ 16.00	\$ 3,008.00
D.009	SP	Sanitary Sewer Bedding Upgrade (Geotextile) *	188	m	\$ 7.00	\$ 1,316.00
D.010	SP	Sanitary Sewer Bedding Upgrade (Crushed Stone) *	188	m	\$ 15.00	\$ 2,820.00
Total Section D - Sanitary						\$ 207,110.00
TOTAL PHAIR AVENUE (5th St. E to 6th St. E.)						\$ 761,360.00

ITEM NO.	OPS SPEC.	DESCRIPTION	EST. QTY	UNIT	UNIT BID PRICE	TOTAL BID PRICE
NELSON STREET (From Butler Ave. 100 metres Easterly) - Drawing A1-348468-P3						
Section A - Grading						
A.001	206, SP	Earth Excavation (Grading)	1,145	m ³ (P)	\$ 12.00	\$ 13,740
A.002	310, SP	Hot Mix HL4 Asphalt	205	t	\$ 256.00	\$ 52,480
A.003	314, SP	Granular 'A'	695	t	\$ 22.00	\$ 15,290
A.004	314, SP	Granular 'B' (Type 1)	1,820	t	\$ 16.00	\$ 29,120
A.005	510, SP	Removal of Asphalt Pavement (Full Depth)	1,514	m ² (P)	\$ 4.00	\$ 6,056
A.006	510, SP	Removal of Curb and Gutter	274	m (P)	\$ 10.00	\$ 2,740
A.007	510, SP	Removal of Concrete Sidewalk	12	m ² (P)	\$ 20.00	\$ 240
A.008	351, SP	Concrete Sidewalk	12	m ²	\$ 366.00	\$ 4,392
A.009	510,351, SP	Remove and Replace Concrete Driveways	45	m ²	\$ 128.00	\$ 5,760
A.010	353, SP	Concrete Curb and Gutter	274	m	\$ 131.00	\$ 35,894
A.011	Section 02930	100 mm Topsoil and Sod	359	m ²	\$ 12.00	\$ 4,308
A.012	510, SP	Boulevard Works Stripping and Removal	1	LS	\$ 3,300.00	\$ 3,300
Total Section A - Grading						\$ 173,320.00
NELSON STREET (From Butler Ave. 100 metres Easterly) - Drawing A1-348468-P3						
Section B - Storm Sewers						
B.001	510, SP	Remove Existing Catchbasins and Manholes	7	ea (P)	\$ 1,000.00	\$ 7,000.00
B.002	510, SP	Remove Existing Catchbasin Leads	36	m (P)	\$ 25.00	\$ 900.00
B.003	510, SP	Remove Existing 750 mm Storm Sewer	30	m	\$ 50.00	\$ 1,500.00
B.004	410, SP	250 mm PVC SDR 35 Catchbasin Leads	45	m	\$ 225.00	\$ 10,125.00
B.005	410, SP	750 mm Storm Sewer	36	m	\$ 1,115.00	\$ 40,140.00
B.006	407, SP	Catchbasins (900 Round Barrel)	6	ea	\$ 2,800.00	\$ 16,800.00
B.007	407, SP	Storm Manhole #2 (OPSD 701.011)	1	ea	\$ 11,000.00	\$ 11,000.00
B.008	407, SP	Catchbasin Manhole #3 (OPSD 701.010)	1	ea	\$ 8,700.00	\$ 8,700.00
Total Section B - Storm Sewers						\$ 96,165.00
NELSON STREET (From Butler Ave. 100 metres Easterly) - Drawing A1-348468-P3						
Section C - Watermain						
C.001	510,441, SP	Remove and Replace Existing Watermain with New 150 mm PVC DR 18 Class 150 Watermain	136	m	\$ 428.00	\$ 58,208.00
C.002	441, SP	150 mm Water Valve and Box	2	ea	\$ 2,400.00	\$ 4,800.00
C.003	SP	50 mm Rigid Styrofoam Insulation	13	m ²	\$ 55.00	\$ 715.00
C.004	441, SP	Remove and Replace 19 mm Copper Water Service and Curb Stops	8	ea	\$ 3,000.00	\$ 24,000.00
C.005	441, SP	Remove and Replace Hydrant Sets	1	ea	\$ 12,200.00	\$ 12,200.00
C.006	441, SP	Temporary Water Service	1	LS	\$ 3,000.00	\$ 3,000.00
Total Section C - Watermain						\$ 102,923.00

* Provisional Item

ITEM NO.	OPS SPEC.	DESCRIPTION	EST. QTY	UNIT	UNIT BID PRICE	TOTAL BID PRICE
NELSON STREET (From Butler Ave. 100 metres Easterly) - Drawing A1-348468-P3						
Section D - Sanitary						
D.001	510, SP	Remove Existing 225 mm and 300 mm Sanitary Sewer	136	m	\$ 25.00	\$ 3,400.00
D.002	510, SP	Remove Existing Sanitary Manhole	1	ea	\$ 1,000.00	\$ 1,000.00
D.003	410, SP	250 mm PVC SDR Sanitary Sewer	15	m	\$ 460.00	\$ 6,900.00
D.004	410, SP	300 mm PVC SDR Sanitary Sewer	121	m	\$ 520.00	\$ 62,920.00
D.005	SP	100 mm Rigid Styrofoam Insulation	328	m ²	\$ 90.00	\$ 29,520.00
D.006	407, SP	Sanitary Manhole	1	ea	\$ 10,000.00	\$ 10,000.00
D.007	410, SP	Remove and Replace Existing 150 mm Sanitary Services	8	ea	\$ 2,700.00	\$ 21,600.00
D.008	410, SP	Temporary Sewer Service	1	LS	\$ 15,000.00	\$ 15,000.00
D.009	409, SP	Closed Circuit Television Inspection of 300 mm Sanitary Sewer Mainline	121	m	\$ 16.00	\$ 1,936.00
D.010	SP	Sanitary Sewer Bedding Upgrade (Geotextile) *	136	m	\$ 7.00	\$ 952.00
D.011	SP	Sanitary Sewer Bedding Upgrade (Crushed Stone) *	136	m	\$ 15.00	\$ 2,040.00
Total Section D - Sanitary						\$ 155,268.00
TOTAL NELSON STREET (From Butler Ave. 100 metres Easterly)						\$ 527,676.00
KINGS HIGHWAY 11-71 - Drawing A1-348468-P4 and P5						
Section A - Grading						
A.001	206, SP	Earth Excavation (Grading) *	6,973	m ³ (P)	\$ 15.00	\$ 104,595
A.002	310, SP	Superpave 12.5	1,760	t	\$ 258.00	\$ 454,080
A.003	310, SP	Superpave 19.0	2,060	t	\$ 263.00	\$ 541,780
A.004	314, SP	Granular 'A'	5,500	t	\$ 25.00	\$ 137,500
A.005	314, SP	Granular 'B' (Type 2) *	9,640	t	\$ 22.00	\$ 212,080
A.006	510, SP	Removal of Asphalt Pavement (Full Depth)	11,734	m ² (P)	\$ 4.00	\$ 46,936
A.007	710, SP	Pavement Markings	1	LS	\$ 30,000.00	\$ 30,000
A.008	510, SP	Removal of Curb and Gutter	210	m	\$ 10.00	\$ 2,100
A.009	353, SP	Concrete Curb and Gutter (Hand Formed)	210	m	\$ 230.00	\$ 48,300
A.010	SP	Geogrid (Terrafix TBX3000 or Equivalent) *	10,728	m ²	\$ 6.00	\$ 64,368
A.011	510, SP	Removal of Concrete Sidewalk	195	m ²	\$ 30.00	\$ 5,850
A.012	351, SP	Concrete Sidewalk	195	m ²	\$ 210.00	\$ 40,950
Total Section A - Grading						\$ 1,688,539.00
KINGS HIGHWAY 11-71 - Drawing A1-348468-P4 and P5						
Section B - Storm Sewers						
B.001	407, SP	Catchbasins	4	ea	\$ 2,800.00	\$ 11,200.00
B.002	407, SP	Storm Manholes #3, #5 and #6	3	ea	\$ 11,000.00	\$ 33,000.00
B.003	407, SP	Storm Manholes #4 and #7	2	ea	\$ 11,000.00	\$ 22,000.00
B.004	410, SP	300 mm Storm Sewer	176	m	\$ 539.00	\$ 94,864.00
B.005	410, SP	250 mm Catchbasin Leads	37	m	\$ 225.00	\$ 8,325.00
B.006	410, SP	Remove and Replace Existing 1200 mm Storm Sewer	24	m	\$ 1,190.00	\$ 28,560.00
B.007	408, SP	Supply and Install Adjustable Storm Manhole Covers	2	ea	\$ 1,350.00	\$ 2,700.00
Total Section B - Storm Sewers						\$ 200,649.00

* Provisional Item

ITEM NO.	OPS SPEC.	DESCRIPTION	EST. QTY	UNIT	UNIT BID PRICE	TOTAL BID PRICE
KINGS HIGHWAY 11-71 - Drawing A1-348468-P4 and P5						
Section C - Watermain						
C.001	510,441, SP	Remove Existing 100/150 mm Watermain	612	m	\$ 25.00	\$ 15,300.00
C.002	441, SP	150 mm Dia. Watermain	875	m	\$ 500.00	\$ 437,500.00
C.003	441, SP	150 mm Water Valve and Box	13	ea	\$ 2,400.00	\$ 31,200.00
C.004	441, SP	Remove and Replace 19 m Copper Water Service	19	ea	\$ 3,000.00	\$ 57,000.00
C.005	441, SP	Remove and Replace Hydrant Sets	3	ea	\$ 12,200.00	\$ 36,600.00
C.006	441, SP	Temporary Water Service	1	LS	\$ 23,000.00	\$ 23,000.00
C.007	441, SP	Cap Existing 150 mm Watermain	2	ea	\$ 500.00	\$ 1,000.00
Total Section C - Watermain						\$ 601,600.00
KINGS HIGHWAY 11-71 - Drawing A1-348468-P4 and P5						
Section D - Sanitary						
D.001	408, SP	Supply and Install Adjustable Manhole Covers	3	ea	\$ 1,350.00	\$ 4,050.00
D.002	510, SP	Remove Existing 300 mm Sanitary	254	m	\$ 25.00	\$ 6,350.00
D.003	410, SP	300 mm Sanitary Sewer	250	m	\$ 520.00	\$ 130,000.00
D.004	410, SP	Remove Existing Sanitary Manholes	3	ea	\$ 1,000.00	\$ 3,000.00
D.005	410, SP	New Sanitary Manholes	3	ea	\$ 10,000.00	\$ 30,000.00
D.006	SP	Temporary Sewer Service	1	LS	\$ 10,000.00	\$ 10,000.00
D.007	SP	New Sanitary Services	19	ea	\$ 2,500.00	\$ 47,500.00
D.008	SP	Closed Circuit Television Inspection of 300 mm Sanitary Sewer	248	m	\$ 13.00	\$ 3,224.00
D.009	SP	Sanitary Sewer Bedding Upgrade (Geotextile) *	250	m	\$ 7.00	\$ 1,750.00
D.010	SP	Sanitary Sewer Bedding Upgrade (Crushed Stone) *	250	m	\$ 15.00	\$ 3,750.00
Total Section D - Sanitary						\$ 239,624.00
TOTAL KINGS HIGHWAY 11-71						\$ 2,730,412.00
SECTION G - GENERAL						
G.001		Bonds & Insurance	1	LS	\$ 130,000.00	\$ 130,000.00
G.002		Mobilization & Demobilization	1	LS	\$ 266,000.00	\$ 266,000.00
G.003		Traffic Control	1	LS	\$ 75,000.00	\$ 75,000.00
G.004		Contingency Allowance	1	LS	\$ 250,000.00	\$ 250,000.00
TOTAL SECTION G - GENERAL						\$ 721,000.00

* Provisional Item

ITEM NO.	OPS SPEC.	DESCRIPTION	EST. QTY	UNIT	UNIT BID PRICE	TOTAL BID PRICE
SUMMARY OF TENDER PRICES						
PHAIR AVENUE (3rd St. E to 5th St. E)						
		Section A - Grading			\$	366,845.00
		Section B - Storm Sewers			\$	51,525.00
		Section C - Watermain			\$	225,535.00
		Section D - Sanitary			\$	199,810.00
PHAIR AVENUE (3rd St. E to 5th St. E) Total						\$ 843,715.00
PHAIR AVENUE (5th St. E to 6th St. E.)						
		Section A - Grading			\$	303,258.00
		Section B - Storm Sewers			\$	15,600.00
		Section C - Watermain			\$	235,392.00
		Section D - Sanitary			\$	207,110.00
PHAIR AVENUE (5th St. E to 6th St. E.) Total						\$ 761,360.00
NELSON STREET (From Butler Ave. 100 metres Easterly)						
		Section A - Grading			\$	173,320.00
		Section B - Storm Sewers			\$	96,165.00
		Section C - Watermain			\$	102,923.00
		Section D - Sanitary			\$	155,268.00
NELSON STREET (From Butler Ave. 100 metres Easterly) Total						\$ 527,676.00
KINGS HIGHWAY 11-71						
		Section A - Grading			\$	1,688,539.00
		Section B - Storm Sewers			\$	200,649.00
		Section C - Watermain			\$	601,600.00
		Section D - Sanitary			\$	239,624.00
KINGS HIGHWAY 11-71 Total						\$ 2,730,412.00
SECTION G - GENERAL						
General Total						\$ 721,000.00
SUB-TOTAL					\$	5,584,163.00
13% HST					\$	725,941.19
TOTAL TENDER PRICE					\$	6,310,104.19

1.9 DECLARATIONS OF TENDERER

1.9.1 The Tenderer declares that no person, firm or corporation other than the Tenderer has any interest in this tender or in the proposed Contract for which this tender is made.

1.9.2 The Tenderer declares that this tender is made without any connection, comparison of figures or arrangement with, or knowledge of, any other corporation, firm or person making a tender for the same Work and is in all respects fair and without collusion or fraud.

1.10 CONDITIONS OF TENDER

1.10.1 This tender is irrevocable from the official closing time and is unconditionally open for acceptance for 60 days after the official closing time, whether any other tender has been previously accepted or not.


1.11 DISCLAIMER


1.11.1 The Tenderer agrees and acknowledges there is no representation, warranty, collateral agreement or condition, whether direct or collateral, or expressed or implied, which induced the Tenderer to submit this tender, or on which reliance is placed by the Tenderer, or which affects this tender.

1.12 SIGNING OF TENDERS

Dated at Thunder Bay this

8th day of MAY, 2015.


Signature of Tenderer, Title President


Signature of Witness

Signature of Tenderer, Title

Signature of Witness

NOTE: In the case of a tender submitted by a Corporation, the signatory or signatories warrant as follows:

"I/We have authority to bind the Corporation."

"If the tender is submitted by an individual or partnership, it is deemed to be given under seal."

ACCEPTED BY THE CORPORATION OF THE TOWN OF FORT FRANCES

THIS 14th DAY OF May 2015.



Signature

Roy Avis, Mayor

Name and Title



Signature

Witness

Elizabeth Slomka, Clerk

Name and Title

Name and Title