



- NOTES:
1. ALL CONCRETE SHALL BE 32 MPa WITH 5% TO 8% AIR ENTRAINMENT
  2. ALL REINFORCING STEEL SHALL BE GRADE 400 STEEL
  3. ALL REINFORCING BARS TO HAVE 75mm COVER
  4. EXPANSION/CONTROL JOINTS TO BE PROVIDED AT 9m LENGTH AND OR AT CHANGES IN THE WALL CROSS SECTION. PROVIDE EXPANSION JOINTS AT LOCATIONS OF STEP FOOTINGS. PROVIDE 40mm DEEP SAW CUT 3mm-5mm WIDE AND FILL WITH BITUMINOUS FIBER
  5. ALL DIMENSIONS ARE IN mm OR AS NOTED



PROJECT  
RAMP RETAINING WALL  
340 SCOTT ST, FORT FRANCES

CLIENT  
**ZULO  
CONTRACTING Ltd**

DRAWING TITLE  
PLAN VIEW AND SECTION

DATE  
24 AUGUST 2018

